

# Remote Headworks Upgrade

November 4, 2010







# MWRA Sewer System



## Chelsea Creek Headworks

- Comb. and Sep. Trib. Areas (brown shading)
- Flow discharge to North Met Relief Tunnel
- Peak Cap (350 MGD), Avg. Flow (135 MGD)

## Columbus Park Headworks

- Mostly Combined Trib. Areas from Boston (yellow shading)
- Flow discharge to Boston Main Drainage Tunnel
- Peak Cap (182 MGD), Avg. Flow (40 MGD)

## Ward Street Headworks

- Mostly Combined Trib. Areas Cambridge Boston & Brookline with flows from Waltham, Newton & Watertown (darker yellow shading)
- Flow discharge to Boston Main Drainage Tunnel
- Peak Cap (256 MGD), Avg. Flow (90 MGD)

## Headworks Purpose

- Flow control, limited by tunnel capacity and Deer Island Capacity
- Screening and grit removal to protect the downstream tunnels and pumps at Deer Island
- Flow metering to pace DI pumps and measure flow contributions from Boston at WSHW & CPHW.



# Location Plan





# Chelsea Creek Headworks and Screen House – Parcel Boundary




# Columbus Park – property boundary and dog park





# Ward Street Property Boundary with easement and Future MassArt dormitory





# Background

- All built in the 1960s, with major equipment replaced in 1987.
- Some miscellaneous updates since then include a new fuel storage tank and HVAC system at Chelsea Creek; and new roofs, windows and exterior doors at all facilities
- SCADA has been implemented at all three facilities with provision to accommodate additional monitoring and control to be implemented under the upgrade



Chelsea Creek



Columbus Park



Ward Street

# Planned Upgrade

In August of 2009 Malcolm Pirnie completed Concept Design Reports for the headworks. The CDRs include a complete inventory and evaluation of equipment/components at each headworks. It was found that there was an urgent need for extensive upgrading of all three facilities.

The upgrade will include:


- Upgrade to the influent gates used for managing flows.
- Replacement and automation of all solids handling equipment including screens, grit collector systems, and solids conveyance systems
- Replacement of odor control and HVAC systems
- Replacement of ancillary systems, including emergency generators and fuel oil tanks
- Upgrading of instrumentation and control systems
- Security improvements
- New microwave communication towers
- Improvements required to meet applicable Massachusetts State Building Codes
- Improvements to the Building Exterior and Grounds



# Typical Headworks Plan View



# Major Facility Issues to be Addressed (1)



- **Influent Sluice Gates** (4 per facility) are used continuously during storm events to maintain max flows and protect the facility.
- Existing Gates are at the end of their useful life
- Existing Gates do not seat against the influent wall resulting in spraying wastewater during choking operations



- **Climber Screens** (4 per facility) currently require extensive maintenance.
- Screens fail frequently during storm events. If a standby screen is unavailable, additional facility choking is required or bypass of the screening channel over the floor is required.
- Climber screen will be replaced with Catenary screens.




# Major Facility Issues to be Addressed (2)



## Replacement of Grit Collection and Conveyance Systems

- Replacement of Chains and flights
- Conveyance system will be replaced (currently use high pressure air to shoot grit and screening to dumpsters at street level). Final alternative yet to be selected.





# Major Facility Issues to be Addressed (3)



- HVAC Systems are inefficient and are failing requiring replacement.
- Wet Scrubber Odor Control Systems requiring chemical and water will be replaced by Carbon Beds.
- Redundancy and flexibility in HVAC and Odor Control will be provided to ensure worker safety and treatment of odorous air.

# Headworks Upgrade Schedule & Cost

The project is proceeding as one design and one construction project. Design will result in one specification with 3 sets of drawings. NTP issued on July 1, 2010 to Malcolm Pirnie for Contract 7206, Design and Construction Administration Services.

## **Major Milestones:**

Preliminary Design Report:	March 2011
60% Design:	July 2011 (CM Contract 6802 begins)
90% Design:	October 2011
100% Design:	January 2012
Final Bid Documents:	June 2012
Construction NTP:	October 2012
Substantial Completion:	April 2016

## **Associated Costs:**

Contract 7206 (Design and CA): \$6,682,531 (actual)  
Contract 6802 (CM Services): \$6,500,000 (FY 2011 CIP)  
Contract 7161 (Construction): \$81,300,000 (FY 2011 CIP)



# Major Project Challenges

- **Facilities Must maintain Full Capacity and be Fully Operational,** while being gutted and rebuilt. (i.e., 3 of the 4 channels at each facility remain operational at all times).
- **Construction access and staging areas ID will be a challenge.** Much of what is perceived as open space at each facility is actually over the underground grit chambers and will not be available for contractor use. This is a particular problem at Ward Street, where the site is tightest and abuts Wentworth Institute of Technology and MassArt.
- **Determining the Best Means to convey grit and screenings from the operating level to the ground level.**
- **Location of Carbon Towers given Limited Space Around Facilities**
- **Impact of current and future surrounding buildings on construction, operations and maintenance. (MassArt Dorms, etc.)**
- **Selecting Architectural options for physical enhancement of the headworks Building Exteriors.**