

Wastewater Advisory Committee

Wastewater Pipeline Inspection and Maintenance

Stephen Cullen Kenneth Bates


March 3, 2017



Today's Agenda

- Overview of MWRA Sewer System
- Pipeline Inspection
- Pipeline Maintenance
- Pipeline Renewal








Sewers by Type

Sewer Type	Miles	Percent		
Gravity Sewers	227	82%		
Cross-Harbor Tunnels	18.1	6.5%		
Force Mains	20	7.2%		
Siphons	7	2.5%		
CSO Outfalls	3.4	1.2%		
Storage Tunnels	2.2	0.6%		
Total	275.5	100%		




Wastewater Pipeline Work Order History





MAINTENANCE Work order by type



PM – Preventative Maintenance

CM – Corrective Maintenance

EM – Emergency Maintenance



Wastewater Pipeline TV Inspection

Function/Responsibilities

TV Inspection

- Closed Circuit Television Inspection(CCTV) of MWRA Interceptors
- Structure Inspections Manhole, Tide gate, Diversion, Junction
 & Head House Pole Camera System
- Siphon Inspection Sonar Camera System
- Wet Weather System Monitoring

Community Assistance

CCTV of Member Community Sewer Systems as Requested



Inspection Goals Gravity Pipeline, Siphon Barrels, Structures

- CCTV Inspect 32 Miles/13% of the system annually.
 The entire gravity system(227 miles) is inspected once every 7 years.
- Inspect 20 Siphons(48 individual barrels)/44% of the system annually.

 The entire siphon system(61 siphons, 109 individual barrels) is inspected once every 3 years.
- Inspect 650 structures/16% of the system annually.

 The entire structure system(4,000 structures) is inspected once every 6 years.



Wastewater Pipeline TV Inspection/Maintenance

Wastewater Pipeline Performance Measure

TV Inspections	<u>FY17</u>	YTD
Sewer Line CCTV Inspections (Miles)	32	24.12
Siphon Inspections (Number of Barrels)	48 (2.3 miles)	28
Structure Inspections (Includes Manholes, Head Houses,	650	555
Diversion, Tide Gate and Junction Structures)		
Wastewater Pipeline		
Interceptor Cleaning (Miles)	36	24.28
Siphon Cleaning (Number of Barrels)	36 (1.7 miles)	44
Manhole Frame and Cover Replacement	108	99



Massachusetts Water Resources Authority Manhole Inspection Work Order FOD

TIprint,rptdesign 2017-03-01 14:22:53.563

WO#: FO-3508

MWRA ID: SPIPES:626.0/0054+06-0053+85

Description: VACTOR SIPHON SECTION 626, SMELT BROOK WEYMOUTH
Asset: 87756 PIPE SEGMENT WRA-6260-0054+06 -

WRA-6260-0053+2385

Location; SEWERPIPE SEWERAGE PIPELINE HIERARCHY

Job Plan; VACTOR1 UTILIZE VACTOR TRUCK FOR MAINTENANCE ON SEWER

 Supervisor: SALAMONE_A
 Report Date: 02/01/2017 01:03:10 PM

 Planner: ANAYA_M
 Target Start: 01/25/2017 01:03:00 PM

Requester: ANAYA_M Target Finish:
Crew ID: Priority: 3

Status: INPRG

Workt Type: CM Sub Type: VJ PM #:

Route: Master WO: Contract:

2000	TO A STATE OF THE									
	Tasks									
Task ID	description									
5	ENSURE THAT ALL EMPLOYEES FOLLOW ALL MWRA SAFETY PROCEDURES AND PROTOCALS									
	Follow appropriate safety measures and procedures including but not limited to: hardhats with faceshields, safety glasses, hearing protection, appropriate respiratory protection, gloves, protective coveralls, reflective vests, safety boots etc. Follow all traffic safety measures: sign boards, cones, caution tape, barriers, lights, police detail as required etc. Follow all Confine Space Entry requirements: gas monitor, tripod, harness, fall retrieval, lights, radio as required etc.									
10	MEET WITH SUPERVISOR TO DISCUSS JOB PLAN AND WORK SEQUENCING.									
20	OBTAIN RELEVANT PLANS, DETAIL RECORDS, MAPS, AND PAST									
30	inspection reports for sewer segment / structure selected for maintenance. ARRANGE FOR SUPPORT CREWS AND CALL FOR POLICE DETAILS									
	if needed.									
40	PREPARE AND MOBILIZE VEHICLES AND EQUIPMENT NEEDED									
	to perform job tasks. Insure all equipment is in good working condition and fueled up before leaving to planned job site. Fill vactor truck with water as needed,									
50	UPON ARRIVAL AT WORK SITE FOLLOW ALL SAFETY PROCEDURES									
	and set up barriers to prevent unauthorized persons from entering job sites.									
60	AS REQUIRED COMMUNICATE WORK LOCATION TO THE OCC									
	and follow all CSE procedures before opening or entering any sewer segment / structure.									
70	SAFELY POSITION VACTOR TRUCK AT SEWER SEGMENT / STRUCTURE									
	to begin vactor / jetting operation. Reposition equipment as needed in order to complete planned job tasks. Stop cleaning at full tank alarm									
80	REPORT AND RECORD ANY MAJOR DEFICIENCIES OR OBSTRUCTIONS									
	to your supervisors.									
90	AFTER COMPLETION OF JOB TASKS BREAK DOWN WORK SITE,									
	Restore site to its original condition.									
100	EMPTY VACTOR AT THE SOMERVILLE MARGINAL CSO.									
	Record total amount of debris removed from sewer segment / structure. Clean equipment.									
110	AFTER RETURNING TO CHELSEA MAINTENANCE FACILITY									
	service equipment as needed and properly store to assigned area.									
120	TURN IN ALL INSPECTION DOCUMENTS AND COMPLETE THE WORK ORDER ACTUALS									
	and submit them to your supervisor for review.									
130	VACTOR SIPHON									
	Planned Labor									
777										

		Planned Lal	Planned Labor							
laborcode	displayname	craft	Quantity	Est hrs	Rate	Line Total				
		HEO	1	16:00	\$31.00	\$496.00				
		SKILDLBR	1	16:00	\$25.00	\$400.00				
		PIPEFR M	1	16:00	\$37.75	\$604.00				



Closed Circuit Television Inspection(CCTV)






Closed Circuit Television Inspection(CCTV)





Closed Circuit Television Inspection(CCTV) Operator's Room





Closed Circuit Television Inspection(CCTV) Pipe Transporters – Small/Large Pipe





Sonar System – Siphon Inspections











Siphon Inspection Equipment











Walpole Extension Sewer, Norwood

1 - 36" Barrel Siphon Before and After Cleaning











Wastewater Pipeline Maintenance

Maintenance

- Hydraulic Cleaning of MWRA Interceptors/Siphons –Vactor Jet
- Mechanical Cleaning of MWRA Interceptors/Siphons –Bucket Machines
- Manhole Frame and Cover Replacement
- NPDES Monthly Inspections
- Facility Wet Well Cleaning
- Spot Repair- Manhole/Head House Structures and Sewer Pipelines
- Wet Weather Monitoring



Maintenance Goals Gravity Pipeline, Siphon Barrels, Structures

- Maintain 36 Miles/16% of the system annually.
 The entire gravity system(227 miles) is inspected once every 7 years.
- Replace 108 Structure Frames and Covers/2.7% of the system annually.
 The entire structure system(4,000 structures) is inspected once every 6 years.
- Maintain 20 Siphons(36 individual barrels)/33% of the system annually.
 The entire siphon system(61 siphons, 109 individual barrels) is cleaned once every 3 years.



Maintenance Equipment








VACTOR JET PIPE MAINTENANCE





VACTOR JET PIPE MAINTENANCE






MAINTENANCE EQUIPMENT BUCKET MACHINE





SIPHON BARRELL CLEANING EQUIPMENT







SIPHON CLEANING







GREASE/DEBRIS REMOVAL








GREASE / DEBRIS REMOVAL







GREASE/DEBRIS REMOVAL







GREASE/DEBRIS REMOVAL







Maintenance/TV Inspection Training

- Right of Way MBTA
- Railroad Safety Keolis
- Confined Space Entry
- CPR/AED/First Aide
- Right to Know
- Work Zone Safety/Flagger
- Crane & Derrick Rigging/Signal
- ARC Map 9
- OSHA 40 Hour Hazardous Waste
- OSHA 8 Hour Annual Review
- OSHA 10 Hour Construction



Pipeline Renewal Overall Goals

- Prioritize Condition of all Pipelines
- Proactive Replacement/Rehabilitation of Pipelines




Interceptor Renewal Decision Support Model

		CHE OF RES	c of Failure									
	Pi	rimary Facto	rs					Seco	ndary Fa	actors		
2	Description	Code	Weight	Points			Age					Factor
TV Inspection Rating	No Rating	0	0				1	2	3	4	5	Points
TV spectio Rating	A Rating	1	0	200		1	0	0.87	0.12	0.005	0.005	
ST ST	B Rating	2	0.5	200		2	0	0	0	0	0	
	C Rating	3	1		Code	3	0.01	0	0.77	0.15	0.07	
	1-25 yrs	1	0.2	40		4	0	0	0	0	0	
m.	26-50 yrs	2	0.4		Material	5	0	0	0	0	0	20
Age	51-75 yrs	3	0.6		fe	6	0	0	0	0	0	
	76-100 yrs	4	0.8		<i>a</i> ≥	7	0	0	0	0	0	
	101-125 yrs	5	1		Ja 7.5	8	0	0	0	0	0	
	Akron (VTC)	8	1			12	0	0	0	0	0	
	Brick (BR)	2	0.8									
	Cast Iron (CI)	5	0.4									
Material	Ductile Iron (DI)	6	0.4									
ate	Plastic (PL)	12	0.1	40								
Σ	Poured in Place Concrete (PIP)	3	0.75									
	Reinforced Concrete (RC)	1	0.75									
	Steel (STL)	7	0.1									
	Vitrified Clay (VC)	4	1									



MWRA Sewer System Pipelines (by material)





SEWER SIPHON CHAMBER/MANHOLE REHABILITATION











MANHOLE FRAME AND COVER REPLACEMENT





Manhole Frame and Cover Replacement



In House Manhole Frame and Cover Replacement Section 651-High Level Sewer, Station 20+26, Milton



In House Manhole Structure Rehabilitation Section 43 – Metropolitan Sewer, Station 74+30, Cambridge



In House Manhole Structure Rehabilitation Section 43 – Metropolitan Sewer, Station 74+30, Cambridge





MANHOLE STRUCTURE REPLACEMENT



30



MANHOLE STRUCTURE REPLACEMENT





SEWER REHABILITATION – SPOT REPAIR



Completed Rehabilitation of Sections 83 (Arlington) and 160 (Winchester/Medford) using Cured-in-Place Technology





Rehabilitation of Section 156 (MDC 17.5) Everett, MA



CIPP air/steam process






COMPLETED PIPELINE PROJECTS (2004-2016)

	Section No.		2006		Size	Length	Cost Me		Method	Substantial	
Contract	MWRA	MDC	Rank	Location	(in)	(ft)	(\$million)			Completion	Comment
6798	172	93A	N/A	Lexington	36	4,000	\$	1.5	CIPP	2004	Advanced deterioration moved project Up (project awarded before ranking list)
6840	37	37	3 15/25/14	East Boston	41x36	6,000	\$	5.1	CIPP	2005	Scheduled Construction/Condition and Hydraulic Relief
6842	80/82/83	80/82/83		Arlington	20	4,500	\$	1.2	CIPP	2007	Deformed section moved project Up
6843	160/153part	MVS	123/49	Winchester/Medford	28x26	9,500	\$	1.6	CIPP	2008	Deformed section moved project up
6629	529/530 (new686/688)	29/30	115/120	Newton/West Roxbury	15 to 45x48	11,100	\$	8.3	Cut and cover	2008	Scheduled Construction/Condition and Hydraulic Relief (new 685/687)
6191	526/527/528 (new 685/687)		13/22/27	West Roxbury	42	18,500	\$	37.9	Jacking / cut and cover		Scheduled Construction/Condition and Hydraulic Relief (new 685/687)
6841	38/208/207	38/38BR/37BR	34/2/35	East Boston	15	5,300	\$	7.0	Pipe Burst	2010	Scheduled Construction/Condition and Hydraulic Relief
6257	39 (new255/256)	39	1	East Boston	36/48/66	13,000	\$	59.0	MicroTunnel		Scheduled Construction/Condition and Hydraulic Relief (new 255/256)
5310	624	124	283	Weymouth	60x57	2,100	\$	2.5	CIPP	2011	Scheduled Construction/ B-W Hydraulic Relief and poor condition
7393	156	17.5	14	Everett	61x56	1,700	\$	2.5	CIPP	2012	Deteriorating Pipe moved project Up
				Total		75,700	\$ 12	26.6			

MWRA INTERCEPTOR PROGRAM





Questions?